Table of contents

	Drawing Number
Introductory information	
Important notices	GB0-010
Underground Plant Protection information	GB0-020
Code clearances	GB0-025
Commercial/industrial information sheet	GB0-030
Work management	GB0-040
Customer projects engineering district map	GB0-100
Central business district, engineering district map	GB0-110
Distributed generation	GB0-115
Account management executives	GB0-120
Meter installations district map	GB0-130
Construction and maintenance district map	GB0-140
Residential service and small commercial (non-CT metered) installations	GB0-160
Contract coordinator responsibilities	GB0-165
Street lighting district map	GB0-170
Tree trimming work areas	GB0-180

Table of contents

Part 1 - General

	Section
Application for service	100
Inspection for electric service	102
Right to refuse or discontinue service	103
Types of service available	105
Temporary service	107
Rate considerations	110
Fault current levels for the selection of PPE	112
Additional charges	113
Maintaining security of locked facilities	114
Termination of service on building	115
Replacing or maintaining the residential meter fitting	116
Converting from residential overhead to underground service	117
Relocating the residential service point or cable	118
Upgrading a residential underground service lateral	119
Overhead service	120
Height of service drop	125
Underground service lateral within five feet of a pool	127
Length of service drop	130
Extension of lines	135
Clearances to hazardous (classified) locations	137
Easement / rights-of-way / tree trimming	140
Right tree right place	142
Automatic reclosing equipment	145
Continuity of power	146
Single phase protection	147
Phase reversal protection	148
Alterations - changes in size of service	150
Number of services	160
Master metering	162
Maximum size secondary overcurrent device	165
Fire pump installations	170
Distributed generation	175
Duplicate facilities	176
Interconnecting secondary multiple services	177
Foreign attachments	180
Easement encroachments	181
Customer grounds	182
Grounded service conductor	183
DC Decouplers	184
Service demand	185
Fire walls	190
Letter in-lieu of electrical inspection	Page 9A
Letter in-lieu of electrical inspection for temporary electrical service	Page 9B

Table of contents

Part II - Secondary service – other than networked service area

Secondary voltages available	200
Requirements for service	205
Rapidly fluctuating or pulsating loads	210
Underground service	220
Covering and painting of poles	223
Covering, enclosing, and painting of pad mounted equipment	225
Metering enclosure grounding behind service disconnecting means	230
480 V cold sequence meter	235

Part III Secondary service – downtown underground networked service areas

Secondary voltages available	300
Requirements for service	305
Special requirements	310

Part IV - Primary service – other than networked service area

General requirements	400

Part V - Metering

General information	500
Equipment for residential installation	505
Multi-family dwellings	510
Meter centers outside of the downtown underground networked service area	515
Meter centers in the downtown underground networked service area	517
Commercial and industrial metering under 600 volts	520
Outdoor installations - overhead only	525
Transformer mounted CT metering-three phase underground installations only, 450 ampere minimum size service	526
Metering totalization	535
Underground service - non-networked area	540
Switchgear installations	550
Maintaining meter security	555
Installation of SPD & other devices at meter sockets	557
General requirements	560
Unacceptable meter locations	565
Metering on poles and underground facilities	570
Grounding services	575

Table of contents

Part VI - Power quality and electric service reliability

Service reliability	600
Power quality issues	610

Part VII - Secondary services available for roadway, safety, area lighting and traffic signals

Secondary voltages available	700
Requirement for service	705
Applicability of part I and part V	710
Application for traffic signal service	715
Special requirement	720
Special underground requirements	725
Customer supplied concrete column bases	730
Protective posts	735

Illustrations

drawing number

Single phase meter installations

Meter fitting specifications 100, 200, and 320 ampere fittings for 30 to 400 ampere services	GB1-005
100A meter fitting overhead installation 120 volt, 1 phase, 2 wire 30A maximum service	GB1-010
100A meter fitting (installed after main service equipment) 120 volt, 1 phase, 2 wire 30A maximum service	GB1-015
100A meter fitting overhead installation 120/240 volt, 1 phase, 3 wire 125A maximum service	GB1-020
200A meter fitting overhead installation 120/240 volt, 1 phase, 3 wire 225A maximum service	GB1-030
200A meter fitting, 2, 3 or 4 gang overhead installation 120/240 volt, 1 phase, 3 wire 225A maximum service per position	GB1-040

Table of contents

320A meter fitting
overhead installation
120/240 volt, 1 phase, 3 wire
250a to 400A service — GB1-050

100A meter fitting
overhead installation
120/208 volt, 1 phase, 3 wire
125A maximum service — GB1-060

200A meter fitting
overhead installation
residential or temporary
120/208 volt, 1 phase, 3 wire
200A maximum service — GB1-065

100A meter fitting
(installed after main service equipment)
120/208 volt, 1 phase, 3 wire
125A maximum service — GB1-070

200A meter fitting
(installed after main service equipment)
residential or temporary
120/208 volt, 1 phase, 3 wire
200A maximum service — GB1-073

200A meter fitting
(installed after main service equipment)
network installation only
277/480 volt, 1 phase, 3 wire
125A maximum service — GB1-075

200A meter fitting
installed after main service equipment
network installation only
277/480 volt, 1 phase, 3 wire
125A maximum service — GB1-075

200A meter fitting
underground installation
120/240 volt, 1 phase, 3 wire
225A maximum service — GB1-080

200A meter fitting, 2, 3 or 4 gang
underground installation
120/240 volt, 1 phase, 3 wire
225A maximum service per position — GB1-090

320A meter fitting
underground installation
120/240 volt, 1 phase, 3 wire
250A to 400a service — GB1-100

Table of contents

Residential outdoor metering (single family dwelling only) underground installation 120/240 volt, 1 phase, 3 wire 450A to 800A service	GB1-110
Rommercial outdoor metering underground installation 120/240 volt, 1 phase, 3 wire 450A to 800A service	GB1-120
Residential outdoor metering (single family dwelling only) underground installation 120/240 volt, 1 phase, 3 wire 850A to 1600A service	GB1-121
200A single phase residential services 125A single phase commercial services underground installation 120/208 volt, 1 phase, 3 wire 200A maximum service	GB1-130
200A meter fitting (installed after main service equipment) underground installation 120/208 volt, 1 phase, 3 wire 200A maximum service	GB1-140
100A & 200a meter center underground installation 120/240 volt, 1 phase, 3 wire 225A maximum service per position 120/208 volt, 1 phase, 3 wire 200A maximum per position residential 100A maximum per position commercial	GB1-150

Table of contents

Three phase meter installations

200A meter fitting GB3-012
overhead installation
120/208 volt, 3 phase, 4 wire
120/240 volt, 3 phase, 4 wire
225A maximum service

200A meter fitting GB3-013
overhead installation
277/480 volt, 3 phase, 4 wire
225A maximum service

200A meter fitting GB3-015
installed after main service equipment
120/208 volt, 3 phase, 4 wire
120/240 volt, 3 phase, 4 wire
225A maximum service

200A meter fitting, two gang GB3-017
overhead or underground installation
120/208 volt or 120/240 volt, 3 phase, 4 wire
225A maximum service per position

Outdoor metering GB3-020
overhead or trough installation
120/208 volt, 3 phase, 4 wire
120/240 volt, 3 phase, 4 wire
250A to 400A service

Outdoor metering GB3-021
installed after main service equipment
120/208 volt, 3 phase, 4 wire
120/240 volt, 3 phase, 4 wire
250A to 400A service

Outdoor metering GB3-022
underground installation
120/208 volt, 3 phase, 4 wire
120/240 volt, 3 phase, 4 wire
250A to 400A service

Outdoor metering GB3-024
overhead or trough installation
277/480 volt, 3 phase, 4 wire
100A to 400A service

Outdoor metering GB3-026
underground installation
277/480 volt, 3 phase, 4 wire
100A to 400A service

Table of contents

Outdoor metering GB3-028
overhead installation - wall mounted
120/240 volt, 1 phase, 3 wire
120/208 volt, 3 phase, 4 wire
120/240 volt, 3 phase, 4 wire
0A to 400A service
240/480 volt, 1 phase, 3 wire
(interstate lights only)

Outdoor metering GB3-029
overhead installation - wall mounted
120/240 volt, 1 phase, 3 wire
120/208 volt, 3 phase, 4 wire
120/240 volt, 3 phase, 4 wire
277/480 volt, 3 phase, 4 wire
401A to 1600A service
240/480 volt, 1 phase, 3 wire
(interstate lights only)

Outdoor metering GB3-030
overhead installation - wall mounted
120/240 volt, 1 phase, 3 wire
120/208 volt, 3 phase, 4 wire
120/240 volt, 3 phase, 4 wire
277/480 volt 3 phase, 4 wire
1601A to 3000A service

Outdoor metering cabinet GB3-032
transformer rated
overhead installation

Outdoor metering GB3-033
overhead installation
PTs in the meter fitting

200A meter fitting GB3-042
underground installation
120/208 volt, 3 phase, 4 wire
120/240 volt, 3 phase, 4 wire
225A maximum service

200A meter fitting GB3-044
underground installation
277/480 volt, 3 phase, 4 wire
225A maximum service

Outdoor metering GB3-060
underground installation
120/208 or 120/240 volt, 3 phase, 4 wire
500A to 1200A service

Table of contents

Outdoor metering underground installation 120/208 or 120/240 volt, 3 phase, 4 wire 500A to 1200A service	GB3-070
Delete drawing	GB3-080
Outdoor metering underground installation 277/480 volt 3 phase, 4 wire 250A to 1200A service	GB3-085
Delete drawing	GB3-090
Outdoor metering, underground installation, transformer mounted ct's only 120/208 volt, 3 phase, 4 wire 277/480 volt, 3 phase, 4 wire 450A to 3000A service	GB3-095
Outdoor metering, underground installation transformer mounted ct's only 120/208 volt, 3 phase, 4 wire 450A to 3000A service	GB3-096
Indoor metering 277/480 volt, 3 phase, 4 wire, 250A to 1200A service 120/208 or 120/240 volt, 3 phase, 4 wire 900A to 1200A service	GB3-100
Delete drawing	GB3-105
Delete drawing	GB3-110

Metering compartment for switchgear 120/240 or 120/208V or 277/480V GB3-120

Overhead Service Installations

Overhead service drop clearances up to 400A GB4-005

Quadruplex or triplex service GB4-007

Service connection below roof 400A maximum service GB4-010

Service riser extending through roof 400A maximum service GB4-020

Service riser extending above roof 400A maximum service GB4-030

Temporary overhead construction service 120/240 volt, 1 phase, 3 wire 225A maximum service GB4-040

Temporary pole meter installation for construction 120/240 volt, 1 phase, 3 wire 225A maximum service GB4-050

Permanent pole meter installation for one service 120/240 volt, 1 phase, 3 wire 400A maximum service GB4-060

Typical roof structures for service drop and metering transformers for 600 volts and below GB4-070

Typical roof structures for service drop and metering transformers up to 300 volts services GB4-075

Roof structure for maximum 13.2 kV primary service single conductor cable GB4-080

Primary meter and service disconnecting means GB4-090

Table of contents

Underground service installations

Approved trenching contractors	GB5-005
Residential meter locations for underground service	GB5-010
Underground residential service 400A maximum service	GB5-020
Secondary risers for single and three phase services	GB5-030
New residential service cable installation to foundation	GB5-040
New residential service cable installation to foundation - optional method	GB5-050
Temporary underground construction service 120/240 volt, 1 phase, 3 wire 225A maximum service	GB5-060
Temporary underground construction 120/240 volt, 1 phase, 3 wire 120/208 volt, 1 phase, 3 wire 225A maximum service 120/208 volt, 3 phase, 4 wire 125A maximum service	GB5-070
Single meter pedestal installation for mobile home 120/240 volt, 1 phase, 3 wire 225S maximum service	GB5-080
Single meter pedestal installation 120/240 volt, 1 phase, 3 wire 225A maximum service	GB5-085
200A meter fitting free standing - underground installation 120/240 volt, 1 phase, 3 wire 225A maximum service	GB5-090
200A meter fitting free standing - underground installation 120/240 volt, 3 phase, 4 wire 120/208 volt, 3 phase, 4 wire 225A maximum service	GB5-095
200A meter fitting 277/480 volt, 1 phase, 3 wire 277/480 volt, 3 phase, 4 wire 225A maximum service	GB5-096
Free standing structure for CT metering cabinet-underground installation 120/208, 120/240, 277/480 volt 3 phase, 4 wire 250A to 1200A service	GB5-100

Table of contents

Transformer mounted CT metering only GB5-110
free standing-underground installation
120/208 volt 3 phase, 4 wire
277/480 volt 3 phase, 4 wire
450A to 3000A service

Junction cabinet installations

Typical junction cabinet for multiple services GB6-010
underground installation
600 volts and below, 3 phase, 4 wire
400A maximum service per position

Terminal bar arrangement for junction cabinet GB6-015

Mounting details for junction cabinet GB6-020

Conduit location in junction cabinet for multiple GB6-030
underground services

Typical customer's junction box for 3Ø, multiple 100 and 200 ampere GB6-040
underground services (for maintenance only)

Typical customer's junction box for multiple GB6-050
underground services (for maintenance only)

Typical customer's junction box for multiple GB6-060
underground services (for maintenance only)

Typical customer's junction box GB6-070
underground network service

Miscellaneous information

Standard standoff spacing and riser arrangements 1600A maximum	GB7-010
Concrete pad for single phase transformer 25-167 kVA	GB7-020
Transformer box pad for single phase transformer 25-167 kVA	GB7-030
Concrete pad for three phase transformer 75-1500 kVA	GB7-040
Clearance of telephone and/or cable TV facilities from company pad mounted gear	GB7-050
Normal Spacing for AES Indiana Telephone & Communication Facilities	GB7-055
Maximum available calculated fault currents	GB7-060
Typical weatherhead box interior details 600 volts and below, 3 phase only	GB7-070
Typical weatherhead box fabrication details 600 volts and below, 3 phase only	GB7-080
4.1 kV or 13.2 kV distribution interconnection one-line	GB7-090
208 V or 480 V 3-phase secondary distribution interconnection one-line 500 kVA to 1500 kVA	GB7-100
208 V or 480 V 3-phase secondary distribution interconnection one-line less than 500 kVA	GB7-110
Transfer switch required for backup generation	GB7-115

Outdoor lighting service pedestal installation up to 300 volt services 225A maximum service	GB8-010
Single meter installation 3 wire, 120/240 V, 60A only 3 wire, 120/208 V, 60A only	GB8-020
Single meter installation 3 wire, 120/240 V, 100A max. 3 wire, 120/208 V, 100A max.	GB8-021
Single meter installation 3 wire, 120/240 V, 60A only 3 wire, 120/208 V, 60A only	GB8-030
Permanent traffic signal meter installation for one service 120/240 volt, 1 phase, 3 wire	GB8-035
Permanent pole meter installation for 240/480 volt, 1 phase, 3 wire 200A outdoor lighting service	GB8-040
Free standing – underground installation for 240/480 volt, 1 phase, 3 wire 200A outdoor lighting service	GB8-050
Street light ducts installed for AES Indiana use	GB8-070
Protective posts for light columns	GB8-080
DPW traffic signal combination poles	GB8-085
Installation of customer owned conduit into an AES Indiana pullbox	GB8-090
Concrete base installed by contractor 40 ft. al. column	GB8-100
Concrete base installed by contractor Washington column, single or twin	GB8-110